



**Thiruvananthapuram Regional Co-operative Milk
Producer's Union Limited**

Head Office, Ksheera Bhavan, Pattom, Thiruvananthapuram -
695004.

Ph:0471-2447109, 2446845 Fax: 2449567 E mail:
trcmpu@gmail.com

TRU/HO/PROJ/I/32962/2026

10-09-2026

QUOTATION NOTICE

Sealed quotations are invited from eligible and experienced contractors/agencies for carrying out the Demolition of existing old laboratory RCC slabs and associated brickwork inside the Projects Room, followed by necessary cement plastering and finishing works, as detailed below.

1. Details of Work

Sl. No.	Description	Dimensions	RCC Slab Thickness	Associated Brickwork
1	Slab 1	4.2 m × 0.9 m	15 cm	70 cm
2	Slab 2	1.4 m × 0.8 m	15 cm	70 cm

2. Scope of Work

The work shall include the following:

1. Demolition and removal of the existing RCC slabs and associated brickwork and wall tiles.
2. Breaking, collection, loading and removal of demolition debris from the site.
3. Disposal of debris at an appropriate location as per EIC.
4. Necessary cement plastering of all exposed surfaces after demolition.
5. Finishing and making good the affected areas to ensure proper and safe utilization of the space as an office.
6. Any other incidental work necessary for satisfactory completion of the work.

3. Submission of Quotation

Interested contractors/agencies may submit their quotations in Sealed cover/Email indicating the total amount inclusive of all applicable taxes, labour, materials, transportation, debris disposal and other incidental charges to the following address/Email (trcmpuproj@gmail.com).

Asst Manager (Projects)
TRCMPU Ltd, Milma, Ksheera Bhavan, Pattom.
Pin : 695004

The quotation shall remain valid for a minimum period of 30 days from the last date of submission.

5. Time of Completion

The successful bidder shall complete the entire work within 10 days from the date of issue of the work order.

6. Safety and Responsibility

The contractor shall be responsible for ensuring all necessary safety precautions during the execution of the work. The contractor shall also be responsible for any damage caused to the building, fixtures or other property due to negligence or improper execution of the work.

7. Other Conditions

- The work shall be executed strictly as per the instructions of the authorized officer/site-in-charge.
- The contractor shall arrange all necessary labour, tools, equipment and materials required for execution of the work.
- The site may be inspected by interested bidders before submitting their quotations.
- The department reserves the right to accept or reject any quotation, wholly or partly, without assigning any reason.
- The lowest quotation need not necessarily be accepted if the bidder does not meet the required conditions or specifications.
- Payment shall be made after satisfactory completion of the work and certification by the authorized officer.
- The contractor shall maintain cleanliness at the work site and remove all debris upon completion of the work.

8. Last Date and Time for Submission

Last date for submission of quotation: 17.09.2026

Time: 2.30 PM

Place of submission: TRCMPU Ltd (Projects section), Milma, Ksheera Bhavan, Pattom, Thiruvananthapuram - 4.

Contractors/agencies are requested to submit their quotations in a sealed cover/email (trcmpuproj@gmail.com) superscribed "Quotation for Demolition and Cement Plastering Work in Projects Room."

WILSON M J
MANAGING DIRECTOR(MDO-THO)