

**milma****Thiruvananthapuram Regional Co-operative Milk
Producer's Union Limited**Head Office, Ksheera Bhavan, Pattom, Thiruvananthapuram -
695004.Ph:0471-2447109, 2446845 Fax: 2449567 E mail:
trcmpu@gmail.com

No. 03/TRU/PC/2026

17.06.2026

TENDER NOTICE

Sealed quotations are invited from eligible contractors for carrying out **replacement of damaged floor tiles and associated civil works in the Unit Head's Room at Alappuzha Marketing Cell.**

1. Name of Work:

Replacement of damaged floor tiles along with associated civil works in the Unit Head's Room at Alappuzha Marketing Cell.

2. Scope of Work:

The floor area of the Unit Head's Room is approximately **25 sq. mtr.** Considering the present condition of the flooring, replacement of damaged tiles and completion of all related civil works shall be carried out.

3. Estimated Cost:

₹50,000/- (Rupees Fifty Thousand only), inclusive of cost of materials, labour charges and all allied works.

4. Submission of Tender:

The tender shall be submitted in a **sealed envelope** superscribed with **Tender No. 03/TRU/PC/2026 and Due Date - 30.06.2026.**

The sealed quotation should reach the following address on or before **30.06.2026 at 2.30 PM** and shall be opened on the same day at **3.00 PM.**

Address for Submission:

The Managing Director
TRCMPU Ltd., Milma
Ksheera Bhavan, Pattom P.O.
Thiruvananthapuram - 695004

5. Validity:

The offer shall remain valid for acceptance for a period of **15 days** from the

date of opening of tender.

6. Period of Completion:

The successful contractor shall complete the entire work as per specification within **15 days** from the date of successful receipt of the Work Order.

7. Payment:

Payment shall be released by Unit Head, Alleppy Marketing Cell, upon receipt of certified invoice from Engineering Section, TRCMPU Head Office as follows:

- **100% of the total amount** shall be released after completion of the entire work and after applicable deductions as per specification.

8. Billing and Work Site Address:

Manager, Marketing Cell, TRCMPU Ltd.
Central Products Dairy (CPD) Campus,
Punnapra P.O., Alappuzha - 688004, Kerala

GSTIN 32AAAAT9795J6ZS

9. Material Supply:

All materials required for execution of the work shall be supplied by the Contractor unless otherwise specified in the schedule.

10. General Conditions:

- TRCMPU Ltd. reserves the right to accept or reject any or all tenders without assigning any reason thereof
- The bidder shall have to pay liquidated damages @ 0.5% (Half percentage) per day, for the delay in completion of the work subject to the maximum of 5 % of the order value.
- The TRCMPU shall not be liable for any damage or compensation, in consequence to any accident or injury to any workman or other persons employed by the contractor.
- The work has to be carried out without affecting the day-to-day operation of the office.
- Damage should not occur to the Electrical Installation, Pipe lines, Equipment, Machinery etc. while carrying out the work.

RARARAJ R KAS
MANAGING DIRECTOR

Detailed Bill of Quantities (BOQ) To be filled by bidders

Item No.	Description of Work	DSR Ref.	Unit	Quantity	Rate (₹)	Amount (₹)
1	Dismantling and Removal					
1.1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead: For thickness of tiles 10 mm to 25 mm.	15.23.1	sqm	25		
2	Surface Preparation					
2.1	Hacking of CC flooring including cleaning for surface etc. complete as per direction of the Engineer-in-Charge.	14.83	sqm	25		
3	Supply and Laying Vitrified Tiles					
3.1	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand), Size of Tile 600x600 mm.- Double Charged Vitrified Tile Minimum 8 mm thickness Approved makes: Kajaria/Somany/Johnson/Nitco/equivalent Shade approved by Unit Head	11.41.2	sqm	25		
4	Grouting and Joint Filling					
4.1	Grouting the joints of flooring tiles having joints of 3 mm width, using epoxy grout mix of 0.70 kg of organic coated filler of desired shade (0.10 kg of hardener and 0.20 kg of resin per kg), including filling / grouting and finishing complete as per direction of Engineer-in-charge. Size of Tile 600x600 mm.	11.48.2	sqm	25		

5	Site Cleaning and Disposal				
5.1	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	15.6	cum 1		
	TOTAL COST				
	TAXES				
	GRAND TOTAL				

Name of Bidder:

Sign:

Address:

Seal: